



Large Format Installations with EZ Set Strength & Permeability Built In.



This collaboration between **SEK-Surebond**, **Unilock** and the **Landscape Architecture** team set the foundation for a standout driveway installation using **EZ Set Trass Setting Bed** and **Unilock's** large format pavers. Now, a year later - and after a full Wisconsin winter - the results speak for themselves. No movement, no failure, and the system is performing exactly as intended. It's a great example of how solid planning and quality materials come together to deliver long-term performance and curb appeal.



Large Format Installation Summary: EZ Set Application

Project Size: ~720 sq. ft.

Site Prep:

- 10-12" depth of ¾" angular clear stone base
- Unilock Drive Grid System

Aggregate Details:

- ¾" angular clear for base
- 1/4" - 3/8" angular clear chips for EZ Set Setting Bed
 - ♦ Approximately 20 tons

EZ Set Details:

- Mix ratio: 3:2:1 (stone:water:EZ Set)
- Installed depth: 5" average
- Bags used: 140 (60 lbs each)
- 3 mixers used onsite

Paver Product:

- Unilock
Beacon Hill XL

Edge Restraint:

- EdgeCrete



Scan/[click here](#) for project overview video.



Scan/[click here](#) for EZ Set Tutorial with Hardscape Mentor.

